## **Project Details**

The 82<sup>nd</sup> Dr. Waterline – Phase 2 Project is a Clackamas River Water (CRW) Capital Improvement Project to replace existing waterline. This project consists of laying approximately 1,700 feet of 12-inch diameter ductile iron waterline; including connections to existing waterlines, services and other related facilities. Construction will be along 82<sup>nd</sup> Dr. between Scottstree Way and Hanson Ct. in Clackamas, OR.

Construction Cost: Approximately \$1,000,000

Benefits: This project will replace the existing 1920's era 10-inch waterline on the route. The waterline is beyond its useful

service life, resulting in deteriorated pipeline causing numerous expensive leaks.

## Construction Schedule and Various Impacts

## Schedule:

Design: Jan. 2024 – June 2024 Construction: July 2024 – Nov. 2024 **Time of Day Affected:** Monday – Friday, 7:00 a.m. – 5:00 p.m. (Occasional night shift work may be required)

**Impact:** Construction activity will produce noise, dust and diesel equipment fumes during work hours. During construction, there will be open

trenches and equipment in the area such as; large dump trucks, excavators, cutting of pavement, and trench rollers, and compactors. Erosion control and spill prevention will be performed to protect natural resources. Roadways disturbed by the utility work will be repaved at the end of the project. Customers will be notified prior to loss of water service, which will be limited to the duration necessary to carry out the required connections.

**Traffic:** There will be lane restrictions during work hours. Access to local driveways will remain open but they may be impeded for short term work efforts. Emergency access will be provided at all times.

